Registered No. M—1175.

647

The Mysore Gazette.

Vol. 65.] PUBLISHED BY AUTHORITY. [No. 44.

BANGALORE, THURSDAY, NOVEMBER 6, 1930.

PART VI.

PUBLIC ADVERTISEMENTS.

FOREST DEPARTMENT.

OFFICE OF THE CHIEF CONSERVATOR OF FORESTS IN MYSORE.
BANGALORE.

Notification No. D. 2—126-702-30, *dated* 16*th October* 1930.

Letter No. J. 1-703—29-30, dated 24th September 1930, from the Deputy Commissioner, Shimoga, reporting that tigers are doing havoc to village cattle round about District and State Forests of Salur and Kagenahalli, etc., of Shikarpur Taluk and requesting that the area may be thrown open for free shooting of tigers by the villagers for a period of one year, etc.

In virtue of powers vested in the Chief Conservator of Forests, it is hereby ordered that the local villagers living round about Salur, Kagenahalli and other blocks of Shikarpur Taluk, may shoot tigers without a license, for a period of three months from the date of this notification within the limits of the villages of Shikarpur Taluk.

B. V. RAMAIENGAR,
Chief Conservator of Forests.

ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Dated 28*th October* 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 25th November 1930, for Restoring Thimmanahalli Kanavekere, Regd. No. 858, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed, "Tender for Restoring Thimmanahalli Kanavekere, Bagepalli Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive [illegible] does not bind himself to accept the lowest or [illegible] for the rejection [illegible]

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tender must quote specific rates for all items both in words and figures.

10. The tender stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate for restoring Thimmanahalli Kanivekere Regd. No. 858 of Bagepalli Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	I Bund.		Rs. a. p.		
1	Earthwork with watering and tamping for consolidation with lead and lift, etc.	C.yds.		2,530	
2	Turfing	S yds.		1,049	
3	Removing and resetting old stone revetment with new jelly.	C.yds.		1,715	
4	New stone work	,,		370	
5	B. M. stones	No.		2	
6	Grade stones including carving and painting figures, etc, complete.	,,		15	
7	Index stones	,,		15	
8	Gauge stone	,,		1	
9	Register No. stone	,,		1	
10	Cutting trenches and removing ant-hills, prickly pears, etc.	Grade		13	
	II. Sluice at R. L. 38·00.				
1	Earthwork	C.yds.		326	
2	Refilling the sluice gap, watering and tamping...	,,		285	
3	Surki concrete	C.ft.		387	
4	Burnt brick in surki mortar	,,		1,187	
6	Burnt stone slabes 6" thick	S.ft.		389	
6	Surki mortar plastering	Sqr.		13·14	
7	Providing plug and rod with lacking system ...	Lump		sum Rs.	
8	Cutting holes to orifice and cross slabs ..	No.		4	
	III. Left Weir at 50·00.				
1	Attending for necessary repairs to left weir apron.	Lump		sum Rs.	
	IV. Right Weir at 50·00.				
1	Draft and approach clearing including cut opening the bund up to 50·00.	Lump		sum Rs.	
2	Earthwork	C.yds.		154	
3	Surki concrete	C.ft.		252	
4	Burnt brick is surki mortar	,,		479	
5	Burnt stone slabs of 6" thick	S.ft.		376	
6	Plastering with surki mortar	Sqr.		7·76	
7	New stone work	C.yds.		123	
	Total ...	...		...	
	Contingencies ...	...		...	
	Grand Total ...	...		...	